

Rehabilitation Phase - 2

Project No. BRCRLR5355D12

February 2, 2022

AGENDA

- ➤Introduction to Project Team
- >WSSC Water Overview
- ➤ Project Overview
- ➤ Project Map
- **▶** Estimated Construction Schedule
- ➤ What to Expect During Construction
- ➤ Project Summary
- ➤ Questions & Answers




Project Team

- ➤ Bhusan Basnet, Design Project Manager Phone: 301-206-7946, Email: <u>Bhusan.Basnet@wsscwater.com</u>
- Timothy Brooks, Technical Contracts Supervisor (Construction) Phone: 443-955-4784, Email: <u>Timothy.Brooks@wsscwater.com</u>
- ➤ Brandon Stewart, Customer Advocate
 Phone: 301-642-1712, Email: <u>Brandon.Stewart@wsscwater.com</u>
- The Wilson T Ballard Company, Engineering Design Consultants



WSSC Water Overview





Project Overview

- WSSC Water is strategically replacing and rehabilitating our aging water and sewer pipes throughout our service area, a part of our effort to enhance service and reliability to our customers.
- The project includes replacing approximately **0.1 mile** of water mains, **0.03 mile** of sewer mains and service lines.
- The current pipes were installed in the 1920's and 1930's and are nearing the end of their life cycle.
- The new water mains will be zinc-coated, ductile iron pipe wrapped in a protective coating, and the sewer mains will be PVC pipe giving the pipes a life expectancy of at least 100 years.
- Replacing the existing pipes will help reduces disruptions to the community, the environment and emergency services due to water main breaks.



Project Overview

- > New water and sewer mains will be installed within the road pavement
- New water house connections (service lines) will be installed from the road pavement to the back of the house for the following properties:
 - Eastern Avenue: 6617, 6621, 6625, 6631, 6633, 6637 and 6701
 - 6702 Westmoreland Avenue
 - 105 Ist Avenue
- New water house connections will be installed from the <u>property line (near sidewalk) to the back</u> of the house for the following properties:
 - Westmoreland Avenue: 6704, 6710, 6800, 6802 and 6814
- New sewer house connection will be installed from the road pavement to the property line for:
 - 105 Ist Avenue



Project Map

Directly Impacted Streets

Eastern Avenue
Ist Avenue
2nd Avenue
Westmoreland
Avenue







PHASE 2

Estimated Construction Schedule

Anticipated Construction Start: March 2022

Estimated Construction Completion: March 2023

*Construction schedules are estimated and weather permitting



Operational Changes in response to Covid-19

- > WSSC Water has implemented protocols that align with recommendations from local, state, and federal public health authorities.
- ➤ Working to minimize impact
 - Facial masks and physical distancing
- ➤ All WSSC Water employees and contractors are required to refrain from coming to work if displaying symptoms of COVID-19.
 - We have implemented robust internal contact tracing and quarantine requirements.
- Earlier notification to customers
 - Contact via handouts





What to Expect During Construction

- ➤ Anticipated Work Hours: Monday-Friday, 9:00 a.m. 3:30 p.m.
 - Work may occasionally extend beyond these hours to complete specific tasks.
 - Nightwork as needed, for multi-lane closure and service shutdown.
- > Construction activities may include:
 - Field reviews and inspections
 - Survey crews
 - Test pits
 - Construction crews and heavy machinery
- Reliable water and sewer service will be maintained during construction
 - Short water shutdowns of up to 8 hours may be required
 - Advanced notification (48-72 hours) of these shutdowns will be provided





What to Expect During Construction

> Open-cut construction method, which involves cutting and excavating a section of the pavement.


> This construction method does create noise and dust.





Traffic Impacts

- > Certain construction activities may require temporary changes to traffic patterns
 - Traffic will be managed to minimize community disruptions
- >Access will be maintained to homes during construction
 - Access into homes is <u>NOT</u> required
 - Access onto private property, outside approved easement area, is generally <u>NOT</u> required



- WSSC Water will provide 48-hour advance (denoted by "No Parking" signs) prior to any parking restrictions
- Any vehicles that have not been removed from the designated area will be towed to a nearby street at no cost to the owner.
- Final restoration of sidewalks, roadways and landscaping will take place within 90 days of construction completion.





notice

Signage and Restoration

- Construction signs with contact persons will be placed throughout the project area
- ➤ Projects completed during the winter months will be permanently paved and restored to their original state or better in the following spring.





Project Summary

- The existing water and sewer mains are near the end of their useful lives.
- ➤ WSSC Water will be installing new water and sewer mains in the roadways, water house connection up to the back of the properties and a sewer house connection up to the property line.
- >WSSC Water will minimize service disruptions during construction.
- >WSSC Water will coordinate work activities with property owners in the project area.
- >WSSC Water will restore all areas impacted by construction activities at the end of the project.
- >WSSC Water's goal is to provide a reliable water system to customers.



THANK YOU! QUESTIONS?

